BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
NO:BBMP/EE/YNK.D/EPMT-01/2020-21 Dt:02-5-2020

APPROVED TENDER SCHEDULE –'B'

Item 65

Name of Work :-Construction of CC road at Chikkabommasandra old village in ward no:04

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri VINAYAKA K R ( )	
				Rate	Rate in Words
1	KSRRB 300: Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 0.5 m. excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)	Cum	37.33	191.81	One Hundred NinetyOne Paise EightyOne Only
2	KSRB M2100-10: Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.89 cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centring complete as per specifications. (P. No-222, I. No-27.18)	Cum	23.30	4830.91	Four Thousand Eight Hundred Thirty Paise NinetyOne Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centring, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2000. Including cost of materials, labour, HOM complete as per specifications. (Page No.271. Item No,37.59.2 of PW, P&IWTD S.R 2018-19)	Cum	7.02	6299.55	Six Thousand Two Hundred NinetyNine Paise FiftyFive Only

	;B M2300-14: Providing T.M.T steel prcement for R.C.C work including straightening, ing, bending, hooking, placing in position, lapping d or welding wherever required, tying with binding ire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour HOM of machinery complete as per specifications. Specification NO. MORTH Specification No.1600 & 2200 TMT Bars Fe 500. (Page No. 239. Item No. 29.29.2 of PW, P&IWTD S.R 2018-19)	Tonne	0.42	65927.09	SixtyFive Thousand Nine Hundred TwentySeven Paise Nine Only
5	Providing and Fixing RCC pre cast cover Slab 100mm thick for drain made out of CC 1:1.5:3 and jelly 20mm Down size with steel reinforcement including form work, lift charges, curing and concrete finished on both sides etc.,CompleteAs per drawing and direction of Engineer IN charge. (Data Rate)	Sqm	31.50	2082.27	Two Thousand EightyTwo Paise TwentySeven Only
6	Construction Un-reinforced, plain cement concrete for pavements using Grade concrete M30 with OPC at 360kg/cum and coarse aggregate 0.69 cum, fine aggregate 0.46 cum. Over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregate at 0.46 cum, Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 Its conforming to IS 9103-2008, mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) & Spreading the concrete with shovels, rackets compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane of impermeable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lined and grades, textured with texturing machine and curing including cost of all materials, labour, hire charges of machineries, all lead and lift charges etc., complete as per specifications.(P. No-176, I. No-22.6.1)	Cum	98.79	4642.97	Four Thousand Six Hundred FourtyTwo Paise NinetySeven Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.